विश्वेश्वरय्या राष्ट्रीय प्रौद्योगिकी संस्थान, दक्षिण अंबाझरी मार्ग, नागपुर–४४००१० (भारत)
VISVESVARAYA NATIONAL INSTITUTE OF TECHNOLOGY, SOUTH AMBAZARI ROAD, NAGPUR – 440 010 (INDIA)
091-0712-2801369, 2801341, 2801815, 2801243, 2801814 Email: storesofficer@vnit.ac.in

WORK ORDER

Ref. No.: VNIT/STR/ELM/RJS/2026-27/97/4743 **Dated:**

16 SEP 2026

To,
Bhagyshree Electrical,
Balaji Nagar, Near Govt. ITI,
Takli (BH), Ta- Saoner,
Dist. Nagpur 441113
Mob.: 9834775044
Email: bhagyshree.corp05@gmail.com

Sub.: Work Order for **New Electrification Work at Newly Proposed Faculty Rooms Adjacent to Conference Room of New Metallurgical and Materials Engineering Department** at VNIT Campus, Nagpur.

The work order as per description below has been awarded to your firm for total cost of **Rs. 1,79,853/-** (incl. of GST) subject to stated Terms & Conditions given below.

Description of Work
New Electrification Work at Newly Proposed Faculty Rooms Adjacent to Conference Room of New Metallurgical and Materials Engineering Department **Details as per Annexure-A**

Terms & Conditions:

1) **Price Basis:** F.O.R. VNIT, Nagpur on delivery basis.
2) **Taxes:** GST @18% included in the above amount or as applicable from time to time.
3) **Delivery Period:** Work to be delivered/completed within 20 Days from the date of work order.
4) **Site of Work:** Faculty Rooms Adjacent to Conference Room of New Metallurgical and Materials Engineering Department.
5) **Payment:** 100% payment on delivery of items & its successful installation / successful completion of work at site and Warranty/Guarantee certificate to be submitted along with the invoice. Contractor shall submit invoice in triplicate along with work completion certificate **and test certificate/ technical data sheet for item no 32 and 34 mentioned in Annexure-A** within 15 days from the date of work completion. Work completion certificate to be submitted with BoQ signed by the Associate Dean(Electrical Works)
6) **Warranty/Guarantee:** Normal comprehensive Warrantee/Guarantee for 01 Year shall be applicable for all items except item no. 32., it will be two years and for item No. 34 will be 05 years as per Annexure-A effective from the date of raising the invoice of the work done.

   Note: "The vendor shall replace any defective material covered under the warranty clause within 48 hours at their own cost and responsibility. No excuses or delays shall be entertained on grounds such as 'the manufacturer has been informed and will inspect/replace the item' or similar reasons. The vendor shall remain solely responsible for ensuring timely replacement and restoration of the material within the stipulated period."
7) Expression of inability for the supply or delivery of good/s as per specifications and make in Annexure-A and VNIT approved make list will lead to cancellation of Work order and institute reserves right to debar the firm/vendor from future tender enquiries and No compensation or payment shall be admissible for the work executed

8) Penalty will be imposed for delay in job completion at rate 0.5% per week subject to maximum of 5% for the work value up to 1 Lakh and Maximum of 10% for the work value exceeding 1 Lakh.

9) Vendor or his workers must follow the instructions given by site engineer for execution of work failing to which will lead to strict actions deemed fit by the institute.

10) Supplier shall be responsible for ensuring safety & security of their workmen at site. In case of any damage, loss or injury to any person / building or to any part thereof, supplier shall repair and make good loss at their own cost.

11) The Vendor must depute only adequately trained, skilled manpower at the work site for execution of the work. In case it is found that any worker is carrying out the work in an unprofessional manner, lacks the requisite skill or training, or fails to comply with the required technical standards, the Institute shall have the right to cancel/terminate the work order. No compensation or payment shall be admissible for the work executed

You are requested to contact the Electrical Maintenance Section for execution of said work. Kindly acknowledge the receipt/acceptance of order.

5/11/14

Dean (P&D)

Copy to: 1] Assoc. Dean (Electrical Works)/A.E., Electrical Maint. Section 2] Dy. Registrar (Accounts) 3] Master File

ANNEXURE - A

Ref. No.: VNIT/STR/ELM/RJS/2026-27/ **Dated:**

Work Order for **New Electrification Work at Newly Proposed Faculty Rooms Adjacent to Conference Room of New Metallurgical and Materials Engineering Department** at VNIT Campus, Nagpur.					
Sr. No.	**Description**	**Qty**	**Unit**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**
1.	Supplying, erecting & terminating FR XLPE insulated, galvanised steel formed wire armoured (strip) cable 1100 V, 4 core 16 sq. mm. copper conductor complete erected with glands & lugs, on wall/ trusses/ pole or laid in provided trench/ pipe as per specification no. CB-LT/CU	39	Mtr.	740.00	28,860.00
2.	Supplying & erecting triple pole and neutral distribution board (TPNDB), SPMCB of 8 ways/phase (24 poles), with door, 1.2mm thickness surface/flush mounted, IP 43 Protection on provided iron/GI frame (horizontal busbar type) as per specification no. SW-MCBDB.	1	Each	2,820.00	2,820.00
3.	Supplying and erecting iron work, purpose with bending, cutting, drilling and welding complete erected at the position with necessary materials duly painted with one coat of red oxide and two coats of enamel paint to match the switchgears or as per directions by the site engineer.	7	Kg.	110.00	770.00
4.	Supplying, erecting & commissioning 4 pole RCCB 63A, electromagnetic type with 30/100/300 mA sensitivity with earth leakage trip indication complete as per specification no. SW-RCCB.	1	Each	2,610.00	2,610.00
5.	Supplying, erecting & marking FP MCB 40A to 63A, with rated short - circuit breaking capacity (Icn) 10kA in provided distribution board as per specification no. SW-MCB	1	Each	1,330.00	1,330.00
6.	Supplying, erecting & marking DP MCB 6A to 32A, C-series with rated short - circuit breaking capacity (Icn) 10kA in provided distribution board as per specification no.SW-MCB	2	Each	47.00	94.00
7.	Supplying, erecting & marking SP MCB 6A to 32A, C-series with rated short – circuit breaking capacity (Icn) 10kA in provided distribution board as per specification no.SW-MCB	8	Each	140.00	1,120.00
8.	Supplying, erecting & marking SP MCB 6A to 32A, B-series with rated short - circuit breaking capacity (Icn) 10kA in provided distribution board as per specification no. SW-MCB	15	Each	135.00	2,025.00
9.	Supplying and erecting modular type D.P. switch 32A with indicator on provided plate and box with wiring connections complete.	3	Each	235.00	705.00
10.	Supplying and erecting PVC Surface modular switch box with double mounting plate for 2 module complete	3	Each	110.00	330.00
11.	Supplying and erecting PVC Surface modular switch box with double mounting plate for 3 module complete.	2	Each	145.00	290.00
12.	Supplying and erecting PVC Surface modular switch box with double mounting plate for 6 module complete	5	Each	179.00	895.00
13.	Supplying and erecting PVC Surface modular switch box with double mounting & front plate for 8 module complete duly connected.	2	Each	220.00	440.00
14.	Supplying and erecting PVC Surface modular switch box with double mounting plate for 12 module complete	3	Each	274.00	822.00
15.	Supplying and erecting modular type 3 pin 6/16A multi socket with safety shutter on provided plate and box with wiring	8	Each	110.00	880.00

	connections complete.				
16.	Supplying and erecting modular type switch 16A on provided plate and box with wiring connections complete.	8	Each	90.00	720.00
17.	Supplying and erecting modular type switch 16/20 A with indicator on provided plate and box with wiring connections complete.	8	Each	95.00	760.00
18.	Supplying and erecting modular type blanking plate one module, on provided plate & box	6	Each	12.00	72.00
19.	Supplying and erecting blanking plate of suitable size on MCBDB	10	Each	12.00	120.00
20.	Point wiring for light/bell hybrid type (surface type under false ceiling and concealed type for drops & switch boards on walls) in min 20 mm HMS PVC conduit / casing n capping with 1.5 sq.mm. (2+1E) FRLSH grade copper wires, modular type switch, earthing and required accessories as per specification no. WG-HW	7	Point	490.00	3,430.00
21.	Point wiring for ceiling fan hybrid type (surface type under false ceiling and concealed type for drops & switch boards on walls) in min 20 mm HMS PVC conduit / casing n caping with 1.5 sq.mm. (2+1E) FRLSH grade copper wires, modular type switch, earthing and required accessories as per specification no. WG-HW	4	Point	490.00	1,960.00
22.	Wiring for plug on board with switch socket surface /concealed type, copper wiring and earthing and with modular accessories as per specification no. WGPW/ CW	16	Point	295.00	4,720.00
23.	Supplying & erecting mains with 2x4 sq.mm FRLSH copper PVC insulated wire laid in provided conduit /trunking/inside pole/bus bars or any other places. as per specification no. WG-MA/BW	172	Mtr.	140.00	24,080.00
24.	Supplying & erecting mains with 2x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/ inside pole/bus bars or any other places. as per specification no. WG-MA/BW	164	Mtr.	95.00	15,580.00
25.	Supplying & erecting mains with 2x1.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit /trunking/ inside pole/bus bars or any other places as per specification no. WG-MA/BW	102	Mtr.	70.00	7,140.00
26.	Supplying and erecting HMS PVC conduit 20 mm dia. with PVC accessories on wall/ceiling as per specification no. WG-MA/CON.	50	Mtr.	24.00	1,200.00
27.	Supplying and erecting HMS PVC conduit 25mm dia. with PVC accessories on wall/ceiling as per specification no. WG-MA/CON.	173	Mtr.	29.00	5,017.00
28.	Supplying and erecting HMS PVC conduit 32mm dia. with PVC accessories on wall/ceiling as per specification no. WG-MA/CON.	97	Mtr.	45.00	4,365.00
29.	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 25mm with accessories on wall/ceiling as per specification no. WG-MA/CON.	53	Mtr.	29.00	1,537.00
30.	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 32mm with accessories on wall/ceiling as per specification no. WG-MA/CON.	49	Mtr.	39.00	1,911.00
31.	Supplying and erecting 25mm dia. corrugated flexible polypropylene conduit	27	Mtr.	17.00	459.00
32.	Supplying and erecting LED Panel Light (600mm X 600mm) Max. 35 W having CRCA powder coated housing, polystyrene diffuser having system lumens output of Min 4200 Lumens, min. efficacy of 120 lumen/W, CRI>80, CCT upto 6500K, Beam Angle of 120 deg., max. ripple of 5%, THD<10%, p.f.>0.95, operating range of 120-270V, surge protection of 2.5 kV, Life class of 50,000 Hrs at L70B50 including driver, having mounting arrangement with board for surface type or spring loaded mounting clips complete **with minimum 2 years warranty as per specification No. FG-IDF/LED.**	8	Each	1,900.00	15,200.00

33.	Supplying & erecting Modular AC box complete with wooden box , MCB, Socket etc suitable for 2 Ton Air Contioner (A.C) (Make Use Only Havells or Crompton)	2	Each	600.00	1,200.00
34.	Supplying and erecting Energy Saving BLDC Ceiling fan 230 V A.C. 50 cycles 1200 mm, Max. Energy Consumption of 28W having service ratio (CMM/W) of Min. 8 , PF>0.9, THD<10% with IR remote control, Temperature Rise of Max. 40 deg.C, having external mounted control PCB completely erected in position as per specification no. FG-FN/CF **Make:- Atomberg, Havells, orient. Normal Comprehensive onsite warranty of five years. Note:- Make of BLDC ceiling fan must be supplied as per the suggestions of Associate Dean(Electrical Works).**	4	Each	3,600.00	14,400.00
35.	Supplying of electronic type step Regulator Socket type suitable for BLDC ceiling fan 1200/1400mm and as per the instructions of site engineer	4	Each	250.00	1,000.00
36.	Supplying and erecting 'B' grade G.I. pipe / M.S. pipe down rod duly painted for fan complete erected with PVC three core flexible cable 1 sq. mm copper PVC wire.	8	Mtr.	180.00	1,440.00
37.	Supplying & fixing anchor type fastener fan hook, with 2 nos. of 10 mm dia x 75 mm long with necessary materials for ceiling fan.	4	Each	100.00	400.00
38.	Supplying & erecting crimping type copper lugs for cable upto 16 sq mm complete as per specification No. CB-CL/CU	18	Each	12.00	216.00
39.	Dismantling the existing light, switch boards, TPNDB/SPNDB, detachable gland plate , Iron pipes independent plug point, wiring including circuit mains of all types along with all accessories and filling of holes with POP etc. complete as per specification no. WG-DM/PW**(approximate total area of the work site is 60 sq. mtr)**	1	Job	1,500.00	1,500.00
				Total Amount	152,418.00
				CGST @ 9%	13,717.62
				SGST @ 9%	13,717.62
				Total Amount FOR VNIT Nagpur	**1,79,853.00**

Note: Materials/items of VNIT approved make list and as per Annexure-A have to be used. Vendor has to provide items of particular make **(Approved Make List/Make specified in Annexure-A)** as per order of Associate Dean (EW). No economic model of material/item should be used. **Sample of each item/material as per Annexure-A need to be shown to Associate Dean (Electrical works) for approval and purchase of items/material should be made by vendor after approval only.**

Any additional requirement will be in the scope of your firm and should be done with no cost to VNIT Nagpur. Test certificate/ Technical Data sheet for item no. 32 and 34 in Annexure-A is to be enclosed

13/9/26

Dean (P&D)

Digitally signed by DHARMESH MADHUKAR PARATE
Date: 2026.09.21 17:47:10 IST
Location: eProcure-EPROC